

Item Number	Item Title	Item Description	Item Quantity	Unit of Measure	Consignee ID	Delivery Period (In days)
	SITC of 15 KVA liquid cooled, three phase, silent type D.G Set with diesel engine with Alternator along with all standred accessories, fuel tank, battery, lead, canopy as per CPCB norms of Govt. of india Manual type including all material, labour, TandP.		1	Number	Jeemdmo	60
219	Supply and burring of Safe Earthing Electrode T-19	Supply and burring of Safe Earthing Electrode T-19 (Hot Dip Galvanized), Length up to 2000mm, outer pipe 50mm, inner pipe 25, terminal Dia 12 mm, outer GI pipe of 16 swg and inner GI pipe of 12 swg with Hot Dip Galvanization up to 100 micron filled with crystalline conductive mixture (CCM) having anti corrosive and conductive property with 50 kgs activated soil (BFC) capable of reducing the soil resistivity with good mixture of retaining capacity along with 30cm square C.I. frame with hinged cover and masonry husing (from electrode terminal to switch board, cost of 25 x 3 G.I . strip will be extra) Make As approved in U.P. P.W.D., and C.P.R.I. Certified	2	Number	Jeemdmo	60
	Supply and laying of 25mm x 3mm G.I. 3strip	Supply and laying of 25mm x 3mm G.I. strip from earth electrode directly in the ground as required complete in all respect.	40	Meter	Jeemdmo	60
	Supply and Fixing of 32 Amp. four pole change over switch	Supply and Fixing of 32 Amp. four pole change over switch on 25mm x 25mm x 3mm angle iron frame, including the cost of labour, TandP, painting and other material required for proper completion of the work as per direction and satisfaction of Engineer in charge	1	Number	Jeemdmo	60

<p>Supply and laying of aluminium conductor PVC insulated armoured served sheathed cables 1100 Volts</p>	<p>Supply and laying of aluminium conductor PVC insulated armoured served sheathed cables 1100 Volts grade at a depth of 750 mm below ground level over a cushion of 75 mm. thick sand all around and protected with burnt bricks on sides and on top. On surface the cable run shall be fixed on M.S. clamps etc. of suitable size or as directed by the Engineer-Incharge, complete in all respect. The armouring of the cable shall be properly connected with the earth conductor by clamps etc. 6 sq. mm 4 core</p>	50Meter	Jeemdmo	60
<p>Supply and fixing of brass nickle plated compression gland</p>	<p>Supply and fixing of brass nickle plated compression gland for PVC insulated and armoured served sheathed, underground cable including rubber ring etc. complete in all respect. The armouring of the cable shall be properly connected with the earth as per direction of Engineer-Incharge. 6 sq. mm 4 core</p>	2Number	Jeemdmo	60
<p>Supply and fixing of plain or pin type copper tin plated cable socket</p>	<p>Supply and fixing of plain or pin type copper tin plated cable socket as per direction of the Engineer-Incharge. 6 sq. mm</p>	8Number	Jeemdmo	60
<p>Making Of DG set foundation with back filling , Concreting Complete in all respect, 8POL etc</p>	<p>Making Of DG set foundation with back filling , Concreting Complete in all respect, POL etc</p>	1Job	Jeemdmo	60

