



आईएलएस स्थापना के लिए सहायक कार्यों के तकनीकी विनिर्देश  
Technical specification of ancillary works for ILS Installation

क्रम संख्या	आइटम/विवरण Items/ Description	तकनीकी विनिर्देश Technical specification
1	SUV Vehicles	Type of Vehicles : SUV with valid RC , Insurance and pollution certificate Vehicles per day :02 Model-2020 onwards Seating capacity per Vehicle: 7+1 Duration of Service required: 28 days AC Provisioning: Yes Driver: YES with valid Driving license Hours of operation per day: 09 hour Total km during service period: 2800 Km/ vehicle Daily Meter Reading Book: Yes Meter counting : From Airport to Airport
2	Manpower	Manpower Category: Semi skilled. ID proof of all manpower: Yes. Per day : 06 no with safety helmet & florescent jacket. Health Condition: All deployed manpower should be Physically fit.
3	Hydra /Crane	Boom Size : 80 Ft or grater . Load Capacity : 15 ton or greater and Last boom load capacity must be 1.5 ton or grater Operator: Yes well trained with valid operating license, Fitness certificate of Hydra/Crane : Required
4	JCB Excavator Machine	Operator: Yes well trained with valid operating license Fitness certificate of JCB & Insurance: Required
5	DGPS Equipment	DGPS along with CAD Software GPS Coordinate to Cartesian coordinate conversion Software) Operator: Yes with educate knowledge of thew system.
6	Total Station	Total Station with CAD Software along Operator: Yes and Must be a Licensed surveyor with educate knowledge of thew system. Date & Time: As per site Engineer
7	Hammer drill	Type of Drill machine: Hammer Size of masonry drill bits: 6 to 14 mm Ø masonry drill bits along with drill operator.
8	Hiring of Gas welding with operator	GAS Welding machine with welder & all kind of welding & Brazing accessories materials
9	Hiring of Truck with Driver and four labour	For Loading ,unloading and Shifting of Equipment's and antenna from One location to another location within the airport premises and any others works instructed by site/project engineer.

  
18/12/2023

  
18/12/2023

  
18/12/2023



1859700/2023/O/o APD(GAYA)-ER

10	Supply of RO Drinking Water with suitable dispenser	2 x 20 Litres jars per day
11	Construction of Earth pits Chamber including construction( using Iron, bricks ,cement and concrete etc) material with lockable cover..	Dimention: 24W*24L*24H Inch. Location : As per instructed by Site Engineer
12	Supply and installation of Retro-reflective Signage non-metalic boards with dual ASTM PVC stand.	30 inch L * 18 Inch H* 3mm thick Signage boards mount on dual 4 feet PVC pipe stand. Installation Location : As per instructed by Site Engineer
13	Supply of First Aid Box	Antiseptic Solution(Dettol etc) 100ml, Antiseptic gel/cream-01 nos, sterilized gauze 05 nos, Sterilized Cotton Roll-01 No, Banded -30 Nos. Antiseptic tape -01 roll, Small scissors 6 inch or bigger-01 no, Hand Sanitizer 500ml- 01 no, Disposable Gloves -12nos Disposable face mask-50 nos Thermometer-01, Pain Relief gel 60 ml-01 , Pain killer tab- 01 strip, Antacid - 100 ml. Crepe Bandage-01 nos Glucose-500 grams
14	Supply of SS NUT( 304 grade ) & bolts M8 Size	Steel Grade -SS 304 Size- M8
15	Supply of Nylon Rope	3/4 inches
16	Supply and installation of C-type insulated Spacers .	suitable for 25mm x 5mm copper strip
17	Disposable paper glasses size 150 ml.	Size-150 ml Material-paper

अमित कुमार, एजीएम (एलेक्स)  
Amit Kumar, AGM (Elex)

चंद्रेश्वर कुमार, एसएम (एलेक्स)  
Chandreshwer Kumar, SM (Elex)

सुजीत कुमार सिन्हा, प्रबंधक (एलेक्स)  
Sujeet Kumar Sinha, Mgr (Elex)